BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2022-23/OW/WORK_INDENT51419

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/01/2022-23, Date: 21-04-2022

Name of Work:Filling of Pot Holes in Ward No. 11, (Kuvempunagara).

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SHANKARREDDY KALLEPALLI ( )	
				In Figures	In Words
1	284.82	Wet Mix Macadam KSRRB M400-17. Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications	Cum	1801.15	Rupees One Thousand Eight Hundred One and Fifteen Paise Only
2	1813.91	Filling Pot-holes and Patch Repairs with Bituminous Concrete, 40 mm KSRRB M3000-5. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3, filling back the pot holes with hot bituminous material as per clause 500.4, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 complete as per specifications	Sqm	292.88	Rupees Two Hundred Ninety Two and Eighty Eight Paise Only

K. Sankar Reddy
Signature of the Contractor

21/04

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92